



MANDELL ENVIRONMENTAL CONSULTING

409 MINNISINK ROAD ♦ SUITE 102 ♦ TOTOWA, NJ 07512 ♦ (973) 785-7574 ♦ FAX (973) 785-0561

Limited Water Sampling Report

Project Name: The Leaguers Head Start

Project Location: 553-567 Orange Street, Newark, NJ

Date of Sampling: November 17, 2023

Limited water sampling was performed by Mandell Environmental Consulting at The Leaguers Head Start, 553-567 Orange Street, Newark, NJ. Water samples were collected from the kitchen sink faucet and water coolers used by the child care center. Samples were also collected from 50% of the other indoor water faucets utilized by the child care. The samples were collected prior to water being used in the building for a minimum of 8 hours and not longer than 48 hours. The samples were collected in 250 milliliter (ml) containers accordance with New Jersey Regulations.

The samples collected were submitted for analysis to Pace Analytical, 575 Broad Hollow Road, Melville, NY 11747, certification # NY158. Samples were analyzed by Graphite Furnace AA, EPA 200.9. The following table contains the results of the sampling. The maximum contaminant level (MCL) for lead in drinking water is 15 ug/L and copper 1,300 ug/L. (Laboratory Results and sampling forms Attached).

Sample Date 11/17/2023

Sample Number	Source	Results Lead	Results Copper	Units	Pos/Neg
553-1	Outlet 1	1.2	9.0	ug/L	Neg.
553-2	Outlet 4	<1.0	<2.0	ug/L	Neg.
553-3	Outlet 6	<1.0	8.8	ug/L	Neg.
553-4	Outlet 13	<1.0	<2.0	ug/L	Neg.
553-5	Outlet 9	1.4	10.6	ug/L	Neg.
553-6	Outlet 10	<1.0	6.2	ug/L	Neg.
553-7	Outlet 16	<1.0	6.4	ug/L	Neg.
553-8	Outlet 17	<1.0	<2.0	ug/L	Neg.
553-9	Outlet 15	<1.0	<2.0	ug/L	Neg.
553-10	Water Cooler 2	<1.0	<2.0	ug/L	Neg.
553-11	Water Cooler 1	<1.0	<2.0	ug/L	Neg.

The laboratory results show that none of the samples were found to exceed the lead in drinking water action level of 15 ug/L and copper 1,300 ug/L. Sampling forms and diagram are attached.

Sampling Performed by: Darren Slack
NJ Lead Inspector/Risk Assessor
Mandell Environmental Consulting
409 Minnisink Road, Suite 102
Totowa, NJ 07512

Signed: Darren Slack Date: 12-7-2023



Pace Analytical Services, LLC
575 Broad Hollow Road
Melville, NY 11747
516-370-6000

November 28, 2023

Stuart Casciano
Mandell Environmental Consulting
409 Minnisink Road
Suite 102
Totowa, NJ 07512

RE: Project: THE LEAGUERS HEAD START 11/17
Pace Project No.: 70278346

Dear Stuart Casciano:

Enclosed are the analytical results for sample(s) received by the laboratory on November 20, 2023. The results relate only to the samples included in this report. Results reported herein conform to the applicable TNI/NELAC Standards and the laboratory's Quality Manual, where applicable, unless otherwise noted in the body of the report.

The test results provided in this final report were generated by each of the following laboratories within the Pace Network:

- Pace Analytical Services - Melville

If you have any questions concerning this report, please feel free to contact me.

Sincerely,

A handwritten signature in cursive script that reads "Kimberley Mack".

Kimberley M. Mack
kimberley.mack@pacelabs.com
516-370-6052
Project Manager

Enclosures



REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



Pace Analytical Services, LLC
575 Broad Hollow Road
Melville, NY 11747
516-370-6000

CERTIFICATIONS

Project: THE LEAGUERS HEAD START 11/17
Pace Project No.: 70278346

Pace Analytical Services Long Island

575 Broad Hollow Rd, Melville, NY 11747

Connecticut Certification #: PH-0435

Delaware Certification # NY 10478

Maryland Certification #: 208

Massachusetts Certification #: M-NY026

New Hampshire Certification #: 2987

New Jersey Certification #: NY158

New York Certification #: 10478 Primary Accrediting Body

Pennsylvania Certification #: 68-00350

Rhode Island Certification #: LAO00340

Virginia Certification # 460302

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: THE LEAGUERS HEAD START 11/17

Pace Project No.: 70278346

Sample: 553-1 OUTLET 1		Lab ID: 70278346001	Collected: 11/17/23 11:30	Received: 11/20/23 15:30	Matrix: Drinking Water			
Parameters	Results	Units	Report Limit	DF	Prepared	Analyzed	CAS No.	Qual
200.8 MET ICPMS Drinking Water		Analytical Method: EPA 200.8 Pace Analytical Services - Melville						
Copper	9.0	ug/L	2.0	1		11/27/23 15:05	7440-50-8	
Lead	1.2	ug/L	1.0	1		11/27/23 15:05	7439-92-1	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: THE LEAGUERS HEAD START 11/17

Pace Project No.: 70278346

Sample: 553-2 OUTLET 4		Lab ID: 70278346002	Collected: 11/17/23 11:30	Received: 11/20/23 15:30	Matrix: Drinking Water			
Parameters	Results	Units	Report Limit	DF	Prepared	Analyzed	CAS No.	Qual
200.8 MET ICPMS Drinking Water		Analytical Method: EPA 200.8 Pace Analytical Services - Melville						
Copper	<2.0	ug/L	2.0	1		11/27/23 15:06	7440-50-8	
Lead	<1.0	ug/L	1.0	1		11/27/23 15:06	7439-92-1	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: THE LEAGUERS HEAD START 11/17

Pace Project No.: 70278346

Sample: 553-3 OUTLET 6		Lab ID: 70278346003	Collected: 11/17/23 11:30	Received: 11/20/23 15:30	Matrix: Drinking Water			
Parameters	Results	Units	Report Limit	DF	Prepared	Analyzed	CAS No.	Qual
200.8 MET ICPMS Drinking Water		Analytical Method: EPA 200.8 Pace Analytical Services - Melville						
Copper	8.8	ug/L	2.0	1		11/27/23 15:08	7440-50-8	
Lead	<1.0	ug/L	1.0	1		11/27/23 15:08	7439-92-1	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: THE LEAGUERS HEAD START 11/17
Pace Project No.: 70278346

Sample: 553-4 OUTLET 13		Lab ID: 70278346004	Collected: 11/17/23 11:30	Received: 11/20/23 15:30	Matrix: Drinking Water			
Parameters	Results	Units	Report Limit	DF	Prepared	Analyzed	CAS No.	Qual
200.8 MET ICPMS Drinking Water		Analytical Method: EPA 200.8 Pace Analytical Services - Melville						
Copper	<2.0	ug/L	2.0	1		11/27/23 15:09	7440-50-8	
Lead	<1.0	ug/L	1.0	1		11/27/23 15:09	7439-92-1	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: THE LEAGUERS HEAD START 11/17

Pace Project No.: 70278346

Sample: 553-5 OUTLET 9		Lab ID: 70278346005	Collected: 11/17/23 11:30	Received: 11/20/23 15:30	Matrix: Drinking Water			
Parameters	Results	Units	Report Limit	DF	Prepared	Analyzed	CAS No.	Qual
200.8 MET ICPMS Drinking Water		Analytical Method: EPA 200.8 Pace Analytical Services - Melville						
Copper	10.6	ug/L	2.0	1		11/27/23 15:11	7440-50-8	
Lead	1.4	ug/L	1.0	1		11/27/23 15:11	7439-92-1	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: THE LEAGUERS HEAD START 11/17
Pace Project No.: 70278346

Sample: 553-6 OUTLET 10		Lab ID: 70278346006	Collected: 11/17/23 11:30	Received: 11/20/23 15:30	Matrix: Drinking Water			
Parameters	Results	Units	Report Limit	DF	Prepared	Analyzed	CAS No.	Qual
200.8 MET ICPMS Drinking Water		Analytical Method: EPA 200.8 Pace Analytical Services - Melville						
Copper	6.2	ug/L	2.0	1		11/27/23 15:12	7440-50-8	
Lead	<1.0	ug/L	1.0	1		11/27/23 15:12	7439-92-1	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: THE LEAGUERS HEAD START 11/17
Pace Project No.: 70278346

Sample: 553-7 OUTLET 16		Lab ID: 70278346007	Collected: 11/17/23 11:30	Received: 11/20/23 15:30	Matrix: Drinking Water			
Parameters	Results	Units	Report Limit	DF	Prepared	Analyzed	CAS No.	Qual
200.8 MET ICPMS Drinking Water		Analytical Method: EPA 200.8 Pace Analytical Services - Melville						
Copper	6.4	ug/L	2.0	1		11/27/23 15:17	7440-50-8	
Lead	<1.0	ug/L	1.0	1		11/27/23 15:17	7439-92-1	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: THE LEAGUERS HEAD START 11/17

Pace Project No.: 70278346

Sample: 553-8 OUTLET 17		Lab ID: 70278346008	Collected: 11/17/23 11:30	Received: 11/20/23 15:30	Matrix: Drinking Water			
Parameters	Results	Units	Report Limit	DF	Prepared	Analyzed	CAS No.	Qual
200.8 MET ICPMS Drinking Water		Analytical Method: EPA 200.8 Pace Analytical Services - Melville						
Copper	<2.0	ug/L	2.0	1		11/27/23 15:19	7440-50-8	
Lead	<1.0	ug/L	1.0	1		11/27/23 15:19	7439-92-1	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: THE LEAGUERS HEAD START 11/17

Pace Project No.: 70278346

Sample: 553-9 OUTLET 15		Lab ID: 70278346009	Collected: 11/17/23 11:30	Received: 11/20/23 15:30	Matrix: Drinking Water			
Parameters	Results	Units	Report Limit	DF	Prepared	Analyzed	CAS No.	Qual
200.8 MET ICPMS Drinking Water		Analytical Method: EPA 200.8 Pace Analytical Services - Melville						
Copper	<2.0	ug/L	2.0	1		11/27/23 15:20	7440-50-8	
Lead	<1.0	ug/L	1.0	1		11/27/23 15:20	7439-92-1	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: THE LEAGUERS HEAD START 11/17
Pace Project No.: 70278346

Sample: 553-10 WATER COOLER 2 Lab ID: 70278346010 Collected: 11/17/23 11:30 Received: 11/20/23 15:30 Matrix: Drinking Water

Parameters	Results	Units	Report Limit	DF	Prepared	Analyzed	CAS No.	Qual
200.8 MET ICPMS Drinking Water		Analytical Method: EPA 200.8 Pace Analytical Services - Melville						
Copper	<2.0	ug/L	2.0	1		11/27/23 15:22	7440-50-8	
Lead	<1.0	ug/L	1.0	1		11/27/23 15:22	7439-92-1	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



ANALYTICAL RESULTS

Project: THE LEAGUERS HEAD START 11/17

Pace Project No.: 70278346

Sample: 553-11 WATER COOLER 1 Lab ID: 70278346011 Collected: 11/17/23 11:30 Received: 11/20/23 15:30 Matrix: Drinking Water

Parameters	Results	Units	Report Limit	DF	Prepared	Analyzed	CAS No.	Qual
200.8 MET ICPMS Drinking Water		Analytical Method: EPA 200.8 Pace Analytical Services - Melville						
Copper	<2.0	ug/L	2.0	1		11/27/23 15:23	7440-50-8	
Lead	<1.0	ug/L	1.0	1		11/27/23 15:23	7439-92-1	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: THE LEAGUERS HEAD START 11/17
Pace Project No.: 70278346

QC Batch: 328784 Analysis Method: EPA 200.8
QC Batch Method: EPA 200.8 Analysis Description: 200.8 MET No Prep Drinking Water
Laboratory: Pace Analytical Services - Melville
Associated Lab Samples: 70278346001, 70278346002, 70278346003, 70278346004, 70278346005, 70278346006, 70278346007, 70278346008, 70278346009, 70278346010, 70278346011

METHOD BLANK: 1682422 Matrix: Water
Associated Lab Samples: 70278346001, 70278346002, 70278346003, 70278346004, 70278346005, 70278346006, 70278346007, 70278346008, 70278346009, 70278346010, 70278346011

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Copper	ug/L	<2.0	2.0	11/27/23 14:50	
Lead	ug/L	<1.0	1.0	11/27/23 14:50	

LABORATORY CONTROL SAMPLE: 1682423

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Copper	ug/L	50	46.3	93	85-115	
Lead	ug/L	50	48.0	96	85-115	

MATRIX SPIKE SAMPLE: 1682425

Parameter	Units	70278345007 Result	Spike Conc.	MS Result	MS % Rec	% Rec Limits	Qualifiers
Copper	ug/L	5.5	50	48.6	86	70-130	
Lead	ug/L	<1.0	50	45.9	92	70-130	

MATRIX SPIKE SAMPLE: 1682427

Parameter	Units	70278345008 Result	Spike Conc.	MS Result	MS % Rec	% Rec Limits	Qualifiers
Copper	ug/L	<2.0	50	47.1	94	70-130	
Lead	ug/L	<1.0	50	47.7	95	70-130	

SAMPLE DUPLICATE: 1682424

Parameter	Units	70278345007 Result	Dup Result	RPD	Qualifiers
Copper	ug/L	5.5	5.5	0	
Lead	ug/L	<1.0	<1.0		

SAMPLE DUPLICATE: 1682426

Parameter	Units	70278345008 Result	Dup Result	RPD	Qualifiers
Copper	ug/L	<2.0	<2.0		

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA

Project: THE LEAGUERS HEAD START 11/17

Pace Project No.: 70278346

SAMPLE DUPLICATE: 1682426

Parameter	Units	70278345008 Result	Dup Result	RPD	Qualifiers
Lead	ug/L	<1.0	<1.0		

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALIFIERS

Project: THE LEAGUERS HEAD START 11/17
Pace Project No.: 70278346

DEFINITIONS

DF - Dilution Factor, if reported, represents the factor applied to the reported data due to dilution of the sample aliquot.
ND - Not Detected at or above adjusted reporting limit.
TNTC - Too Numerous To Count
J - Estimated concentration above the adjusted method detection limit and below the adjusted reporting limit.
MDL - Adjusted Method Detection Limit.
PQL - Practical Quantitation Limit.
RL - Reporting Limit - The lowest concentration value that meets project requirements for quantitative data with known precision and bias for a specific analyte in a specific matrix.
S - Surrogate
1,2-Diphenylhydrazine decomposes to and cannot be separated from Azobenzene using Method 8270. The result for each analyte is a combined concentration.
Consistent with EPA guidelines, unrounded data are displayed and have been used to calculate % recovery and RPD values.
LCS(D) - Laboratory Control Sample (Duplicate)
MS(D) - Matrix Spike (Duplicate)
DUP - Sample Duplicate
RPD - Relative Percent Difference
NC - Not Calculable.
SG - Silica Gel - Clean-Up
U - Indicates the compound was analyzed for, but not detected.
N-Nitrosodiphenylamine decomposes and cannot be separated from Diphenylamine using Method 8270. The result reported for each analyte is a combined concentration.
Reported results are not rounded until the final step prior to reporting. Therefore, calculated parameters that are typically reported as "Total" may vary slightly from the sum of the reported component parameters.
Pace Analytical is TNI accredited. Contact your Pace PM for the current list of accredited analytes.
TNI - The NELAC Institute.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.



QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: THE LEAGUERS HEAD START 11/17

Pace Project No.: 70278346

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
70278346001	553-1 OUTLET 1	EPA 200.8	328784		
70278346002	553-2 OUTLET 4	EPA 200.8	328784		
70278346003	553-3 OUTLET 6	EPA 200.8	328784		
70278346004	553-4 OUTLET 13	EPA 200.8	328784		
70278346005	553-5 OUTLET 9	EPA 200.8	328784		
70278346006	553-6 OUTLET 10	EPA 200.8	328784		
70278346007	553-7 OUTLET 16	EPA 200.8	328784		
70278346008	553-8 OUTLET 17	EPA 200.8	328784		
70278346009	553-9 OUTLET 15	EPA 200.8	328784		
70278346010	553-10 WATER COOLER 2	EPA 200.8	328784		
70278346011	553-11 WATER COOLER 1	EPA 200.8	328784		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

WO#: 70278346



CHAIN-OF-CUSTODY / Analytical Request Document

The Chain-of-Custody is a LEGAL DOCUMENT. All relevant fields must be completed accurately.

70278346

Section A Requested Client Information: Company: <u>ENVIRONMENTAL</u> Address: <u>107 Municipal Road</u> Suite 102 Totowa, NJ 07512 Phone: <u>973-785-7574</u> Fax: <u>973-785-0564</u> Requested Due Date/AT: _____		Section B Requested Project Information: Report To: _____ Copy To: _____ Purchase Order No.: _____ Project Name: <u>The Leagues Head Shaft</u> Project Number: _____		Section C Invoice Information: Attention: _____ Company Name: <u>S.M. Miller</u> Address: _____ City: _____ State: _____ Zip: _____ Project Manager: _____ Project Profile #: _____		Page: _____ of _____ 2054209	
REGULATORY AGENCY ☐ NPDES ☐ GROUND WATER ☒ DRINKING WATER ☐ UST ☐ RCRA ☐ OTHER _____ Site Location: <u>53-567 Orange Street</u> State: <u>NJ</u> Newark, NJ							

ITEM #	Section D Requested Client Information Sample ID's MUST BE UNIQUE (A-Z, 0-9 / -)	Matrix Code (see valid codes to left)	Sample Type (G=GRAB C=COMP)	COLLECTED		DATE	TIME	DATE	TIME	SAMPLE TEMP AT COLLECTION	# OF CONTAINERS	Preservatives								Analysis Test	Requested, Analysis, Filled (Y/N)	Residual Chlorine (Y/N)	Page Project No./ Lab I.D.		
				COMPOSITE START	COMPOSITE END/DRAW							Unpreserved	H ₂ SO ₄	HNO ₃	HCl	NaOH	Na ₂ S ₂ O ₃	Methanol	Other						
1	53-1 Outlet 1	DW	G			11-17-23	11:30				1														
2	53-2 Outlet 4	DW	G								1														
3	53-3 Outlet 6	DW	G								1														
4	53-4 Outlet 13	DW	G								1														
5	53-5 Outlet 9	DW	G								1														
6	53-6 Outlet 10	DW	G								1														
7	53-7 Outlet 16	DW	G								1														
8	53-8 Outlet 17	DW	G								1														
9	53-9 Outlet 15	DW	G								1														
10	53-10 Water Cooler 2	DW	G								1														
11	53-11 Water Cooler 1	DW	G								1														

ADDITIONAL COMMENTS		RELINQUISHED BY / AFFILIATION	DATE	TIME	ACCEPTED BY / AFFILIATION	DATE	TIME	SAMPLE CONDITIONS	
		Dan Stack	11-17-23	5:00		11-17-23	15:30		
		Melanie AA2	11/17/23	17:45		11/21	4:12		
		MEL PACTA	11/17/23	8:00		11/17/23	8:00	2.6 Y	

SAMPLER NAME AND SIGNATURE	
PRINT Name of SAMPLER: <u>Dan Stack</u>	DATE Signed: <u>11-17-23</u>
SIGNATURE of SAMPLER: <u>Dan Stack</u>	

Temp in °C	Received on Ice (Y/N)	Custody Used Cooler (Y/N)	Seals Intact (Y/N)

WO#: 70278346

PM: KMM
Due Date: 11/30/23
CLIENT: MEC

Client Name: _____ Tracking #: _____
Courier: ☐ Fed Ex ☐ UPS ☐ USPS ☐ Client ☐ Commercial ☒ Pack ☐ Other

Custody Seal on Cooler/Box Present: ☐ Yes ☒ No Seals Intact: ☐ Yes ☒ No Temperature Blank Present: ☐ Yes ☒ No
Packing Material: ☐ Bubble Wrap ☐ Bubble Bags ☐ Ziploc ☒ Other Type of Ice: Wet Blue None
Thermometer Used: ☒ Yes ☐ No Correction Factor: 0.3
Cooler Temperature Corrected (°C): 2.6 Temp should be above freezing to 5.0°C
Cooler Temperature Corrected (°C): 2.9 Date/Time 5035A kits placed in freezer

USDA Regulated Soil (☒ N/A, water sample)
Did samples originate in a quarantine zone within the United States: AL, AR, CA, FL, GA, ID, LA, MS, NC, NM, NY, OK, OR, SC, TN, TX, or VA (check map)? ☐ Yes ☒ No

Did samples originate from a foreign source including Hawaii and Puerto Rico? ☐ Yes ☒ No

If Yes to either question, fill out a Regulated Soil Checklist (ENV-FRM-MELV-0076) and include with SCUR/COC paperwork.

Date and Initials of person examining contents: MRL/24	
1.	Chain of Custody Present: ☒ Yes ☐ No
2.	Chain of Custody Filled Out: ☒ Yes ☐ No
3.	Chain of Custody Relinquished: ☒ Yes ☐ No
4.	Sampler Name & Signature on COC: ☒ Yes ☐ No
5.	Samples Arrived within Hold Time: ☒ Yes ☐ No
6.	Short Hold Time Analysis (<72hr): ☒ Yes ☐ No
7.	Rush Turn Around Time Requested: ☒ Yes ☐ No
8.	Sufficient Volume: (Triple volume provided for MS/MSD) ☒ Yes ☐ No
9.	Correct Containers Used: ☒ Yes ☐ No
10.	-Pace Containers Used: ☒ Yes ☐ No
11.	Containers Intact: ☒ Yes ☐ No
12.	Filtered volume received for Dissolved tests: ☒ Yes ☐ No
13.	Sample Labels match COC: ☒ Yes ☐ No
14.	Matrix: ☒ SL ☐ WT ☐ OIL ☐ OTHER

Date and Initials of person checking preservation: MRL/24	
13.	All containers needing preservation have been ☒ Yes ☐ No ☐ N/A
14.	pH paper Lot # 227822V
15.	All containers needing preservation are found to be in compliance with method recommendation? ☒ Yes ☐ No ☐ N/A
16.	NAOH > 12 Cyanide (HNO ₃ , H ₂ SO ₄ , HCl, NaOH > 9 Sulfide) ☒ Yes ☐ No ☐ N/A
17.	Exceptions: VOA, Coliform, TOC/DOC, Oil and Grease, DRO/8015 (water), Per Method, VOA pH is checked after analysis
18.	Samples checked for dechlorination: ☒ Yes ☐ No ☐ N/A
19.	KI starch test strips Lot #
20.	Residual chlorine strips Lot #
21.	SM 4500 CN samples checked for sul ☒ Yes ☐ No ☐ N/A
22.	Lead Acetate Strips Lot #
23.	Headspace in VOA Vials (>6mm): ☒ Yes ☐ No ☐ N/A
24.	Trip Blank Custody Seals Present: ☒ Yes ☐ No ☐ N/A
25.	Trip Blank Present: ☒ Yes ☐ No ☐ N/A

Client Notification/ Resolution: _____
Person Contacted: _____
Comments/ Resolution: _____
Date/Time: _____
Field Data Required? ☐ Y ☒ N

PM (Project Manager) review is documented electronically in LIMS.

Attachment C - Drinking Water Outlet Inventory (Complete for each school)

Name of School: THE LEARNERS HEAD SMRT Address: 563-567 DANANG STREET
 Grade Levels: _____ Year School Constructed: _____ Renovated/Additions: NEW/AL- N J

Individual school project officer Name/Signature: _____

Date Completed: _____

#	Type	Location	Code	Operational? (Y/N)	Signs of Corrosion (Y/N)	Filter? (Y/N)	Brass Fittings, Faucets or valves? (Y/N)	Aerator/ Screen (Y/N)	Motion Activated (Y/N)	Chiller (Y/N)	Water Cooler Make	Model	Co
1	IWF	CLASS 6 BAN		Y	N	N	N	N	N	N			
2		CLASS 6											
3		CLASS 5											
4		CLASS 5 BAN											
5		BATHROOM											
6		"											
7		STV CLOS.											
8		CLASS 4											
9		CLASS 4 BAN											
10		CLASS 3 BAN											
11		CLASS 3											

IWF = INDOOR WATER FAUCET

WF = WATER FOUNTAIN

WC = WATER COOLER

- Number outlets starting at the closest outlet to the Point of Entry (POE).
- Document if permanently or temporarily out of service on the Attachment B- Plumbing Profile.
- Signs of corrosion detected, such as but not limited to frequent leaks, rust-colored water, or stained fixtures, dishes, or laundry.
- Document on Attachment D- Filter Inventory.

Attachment C - Drinking Water Outlet Inventory

(Complete for each school)

Name of School: THE LEAVES HEADS SMT Address: 563-567 DRAVE STREET

Grade Levels: _____ Year School Constructed: _____ Renovated/Additions: NEWARK NJ

Individual school project officer Name/Signature: _____

Date Completed: _____

Id	Type	Location	Code	Operational ¹ (Y/N)	Signs of Corrosion (Y/N)	Filter ² (Y/N)	Brass Fittings Leaking? (Y/N)	Aerator/ Screen (Y/N)	Monitor Activated (Y/N)	Chiller (Y/N)	Water Cooler Make	Model	Co
12	ITWF	LITTON		Y	N	N	N	N	N	N			
13		"											
14		CLASS 1 BATH											
15		CLASS 1											
16		CLASS 2 BATH											
17		CLASS 2		Y	Y	Y	Y	Y	Y	Y			
18	WC	HALLWAY		Y	N	N	N	N	N	Y	NESTLE	SOS L210	
19	WC	"		Y	N	N	N	N	N	Y	"	"	
20	WTF	"		Y	N	Y	N	N	N	Y			

ITWF = INDOOR WATER FILTER

WC = WATER COOLER

WTF = WATER FOUNTAIN

- Number outlets starting at the closest outlet to the Point of Entry (POE).
- Document if permanently or temporarily out of service on the Attachment B- Plumbing Profile.
- Signs of corrosion detected, such as but not limited to frequent leaks, rust-colored water, or stained fixtures, dishes, or laundry.
- Document on Attachment D- Filter Inventory.

Attachment D - Filter Inventory
(Complete for each school)

(Complete for each school)

Name of School: THE LEAGUES HEAD SMART Grade Levels: _____

Address: 563-567 ORANGE STREET NEWARK NJ

Individual School Project Officer Signature: _____
Date: _____

[illegible]

553-567 Orange St. site

The Leaguers, Inc.

Evacuation Plan

